

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24065-00-00
Spot: CSWNWNE Sec/Twnshp/Rge: 20-11S-18W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: WASINGER Well Number: 2
County: ELLIS Total Vertical Depth: 3540 feet

Operator License No.: 9346
Op Name: DIEHL OIL INC
Address: 1116 VINEYARD RD PO BOX 234
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 2621 W/150 SXS \$115.05
Production: Size 4.5 feet: 3539 W/200 SXS
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/23/2001 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: GLENN DIEHL Company: DIEHL OIL, INC. Phone: (785) 625-6711

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs - LKC 3228', - 3230' and 3348' - 3352' with 2 SPF, AC 1000 G.
TD tool 1240' w/100 sx.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/23/2001 4:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

R.I.H. with tubing to 1195'.
Pumped 125 sxs 60/40 pozmix - 10% gel with 500# hulls.
Circulated 75 sxs to surface with Max. P.S.I. 400#. S.I.P. 150#.

INVOICED
DATE 03-07-2001
INV. NO. 2001061399

Remarks: SWIFT CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

RECEIVED
KANSAS CORPORATION COMMISSION
(TECHNICIAN)

JAN 29 2001


Form CP-2/3

JAN 25 2001

CONSERVATION DIVISION

REPLACEMENT CARD

HELMERICH & PAYNE, INC. 20-11-18W
 P.O. BOX 558 #2 WASINGER SW NW NE
 GARDEN CITY, KS. 67846
 CONTR PIONEER DRILLING CTY ELLIS
 GEOL ALAN DOWNING FIELD BEMIS-SHUTTS
 ELV 1938 KB SPD 10/30/84 CARD ISSUED 1/31/85 IP TEMP ABD
 1933 GL DRLG COMP 11/5/84
 API 15-051-24;065



LOG	Tops	Depth/Datum
ANH	1235+ 703
TOP	2921- 983
HEEB	3151-1213
TOR	3169-1231
LANS	3192-1254
LKC I	3346-1408
BKC	3423-1485
MARM SD	3446-1508
CONG	3455-1517
SIMP	3488-1550
ARB	3516-1578
LTD	3539-1601
RTD	3540-1602

8 5/8 " 262 / 150SX, 4 1/2 " 3539 / 200SX, FO TOOL AT 1240'
 NO CORES OR DST'S
 MICT - CO, PF (LKC) 3228-30 & 3348-52, W / 2 SPF, AC 1000G,
 FRAC 9000G FOAMED FL (15% MSR-100) & SD, SWB DWN, NS,
 PROD NON-COMMERCIAL, TEMP ABD

INFO RELEASED: 10/10/85 ADDED WELL LOGS

WASINGER

COPIED