

15-135-00093-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NESS County. Sec. 24 Twp. 19S Rge. 23E (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner APACHE OIL CORP.  
Lease Name MERTEN Well No. 1  
Office Address 823 SOUTH DETROIT, TULSA, OKLAHOMA  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 9-15 1961  
Application for plugging filed 9-15 1961  
Application for plugging approved 9-15 1961  
Plugging commenced 9-15 1961  
Plugging completed 9-15 1961  
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well GILBERT P. LEIKER, 805 MAIN, VICTORIA, KANSAS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 423 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SURF. CLAY, SHALE, SHELLS</u>	<u>SURF. CSG.</u>	<u>-0-</u>	<u>317'</u>	<u>8-5/8"</u>	<u>317'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**PLUGGED:** LAID DOWN DRILL PIPE. FILLED HOLE UP TO 300'  
WITH MUD. BRIDGED USING 1/3 SK. HULLS,  
HALLIBURTON PLUG, 25 SX. CEMENT THROUGH  
DRILL PIPE. FILLED HOLE TO 40' WITH MUD.  
BRIDGED USING 1/2 SK. HULLS, HALLIBURTON  
PLUG, 10 SX. CEMENT TO CELLAR ZERO.  
2 SX. CEMENT IN RAT HOLE 2' BELOW GROUND  
LEVEL.

JOB COMPLETED: 9 P.M. - 9-15-61.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.  
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. HONAKER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.

BOX 232, RUSSELL, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of SEPTEMBER, 1961

My commission expires 10-17-63



Jerry Lutz  
Notary Public.

APACHE OIL CORP. - Operator

SIERRA PETROLEUM CO., INC - Contr.

MERTEN #1  
C SW SE  
Sec. 24-19S-23W  
Ness County, Kansas

T. D.: 4423'  
Elev.: 2234' K.B.

Commenced: 9-2-61  
Completed: 9-15-61

Casing:  
8-5/8" Set at 317' K.B.

Cement  
with 200 sx. Common

FORMATION	DEPTH
Surface Soil & Clay	35
Shale & Shells	130
Gray Shale & Post Rock	318
Shale	625
Red Bed & Shale	850
Sypsum & Red Bed	960
Gray Shale & Red Bed	1500
Anhydrite	1550
Shale & Slime Streaks	1925
Shale & Shells	2240
Lime & Shale	3750
Lime w/ Shale Streaks	3825
Lime	4229
Lime & Shale	4275
Lime	4380
Mississippi	4423

TOPS:

Anhydrite	1500
Heebner	3694
Lansing Kansas City	3740
Ft. Scott	4260
Conglomerate	4343
Mississippi	4379

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1961

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

C. T. Hancher

Subscribed and sworn to before me this 18th day of September,  
1961.

George D. [Signature]  
Notary Public

My commission expires: 10-17-63

