

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-135-24180-0000

LEASE NAME Antenen

WELL NUMBER 1

660 Ft. from S Section Line

510 Ft. from E Section Line

SEC. 21 TWP. 19 RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 6-5-02

Plugging Commenced 6-5-02

Plugging Completed 6-5-02

RECEIVED

JUN 13 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-5-02 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	344'	Cmtd. w/190 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Push plug to 1,570', pump 50 sax cement on plug thru drill pipe; push plug to 775', pump 80 sax cement on plug thru drill pipe; push plug to 360', pump 50 sax cement on plug thru drill pipe; push plug to 40', dump 10-sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address BOX 709, RUSSELL, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CARMEN SCHMITT, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of June, 2002

My Commission Expires:



Ruth Phillips Notary Public

6-13

Form 0-1