

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-24222-0000

LEASE NAME DM&M

WELL NUMBER 1

430 Ft. from ^N Section Line

810 Ft. from ^W Section Line

SEC. 14 TWP. 19 RGE. 23 NE or SW

COUNTY Ness

Date Well Completed 6-9-03

Plugging Commenced 6-9-03

Plugging Completed 6-9-03

RECEIVED

JUN 19 2003 NOTICE: Fill out completely and return to Cons. Div. office within 30 days.
KCC WICHITA

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-9-03 (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push plug to 1,500', pump 50 sax cement on plug thru drill pipe; push plug to 750', pump 80 sax cement on plug thru drill pipe; push plug to 230', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor (Employee of ~~operator~~ or ~~company~~)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed there the same are true and correct, so help me God.


(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of June, 2003

Luth Phillips
Notary Public

My Commission Expires: _____






15-135-24222-0000
Shields

Russell, Kansas

WELL LOG

Operator: Carmen Schmitt, Inc.
Well: DM&M #1
Commenced: May 30, 2003
Completed: June 9, 2003
Contractor: Shields Drilling Co.

Well Description: Approx. 100'N & 150'E of
S/2 SW SW
Sec. 14-19S-23W
Ness County, KS



RECEIVED

JUN 19 2003

KCC WICHITA

CASING RECORD

Size	Run	Pulled
8 5/8"	217'	Cmtd. w/150 sax

Elevation: 2,199'KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale & rock	220'
Shale	865'
Shale & sand	1,464'
Anhydrite	1,491'
Shale & sand	1,835'
Shale	3,192'
Shale & lime	3,328'
Shale	3,644'
Shale & lime	3,895'
Lime	3,987'
Lime & shale	4,079'
Lime	4,318'
Mississippi	4,375' RTD

Notes