

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25713-00-00  
Spot: NWNESWSW Sec/Twnshp/Rge: 9-17S-14W  
1086 feet from S Section Line, 764 feet from W Section Line  
Lease Name: BEREN TRUST Well #: 2-9  
County: BARTON Total Vertical Depth: 3560 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 445 UNION BOULEVARD SUITE 208  
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	983		380 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/05/2012 12:00 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: GARY TALBOTT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE  
Date/Time Plugging Completed: 07/05/2012 3:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st plug @3475 w/25 sx  
2nd plug @1035 w/40 sx  
3rd plug @420 w/100 sx  
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: BASIC

Plugged through: DP

District: 04

Signed

*Bruce D. Basye*  
7/18/12  
(TECHNICIAN)

CM

JUL 06 2012

JUL 07 2012

RECEIVED

JUL 09 2012

KCC WICHITA