

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20372-00-00
Spot: SWSE Sec/Twnshp/Rge: 5-33S-19W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BAYNE Well #: 1-5
County: COMANCHE Total Vertical Depth: 5505 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4655		
PROD	4.5	5496	1250	WITH 250 SX CMT
SURF	8.625	636		WITH 500 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/28/2012 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5664

Proposed Plugging Method: SET CIBP @ 5065' WITH 2 SX CMT. CUT CASING AT FREE POINT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 30' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE
Date/Time Plugging Completed: 06/28/2012 4:25 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

Perfs:

SET CIBP @ 4655'. COULD NOT GET DOWN HOLE PAST 4750'. CASING PARTED AT 1250'. PULL CASING & RIHWT TO 950'. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 30' WITH 10 SX CMT.

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

RECEIVED
JUL - 5 2012
KCC DODGE CITY

Signed Daniel Bernasconi
7/18/12 (TECHNICIAN)

RECEIVED Form CP-2/3
JUL 09 2012
KCC WICHITA

POINT