

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21471-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 33-22S-7W
510 feet from S Section Line, 630 feet from E Section Line
Lease Name: AYRES Well #: 1-33
County: RENO Total Vertical Depth: 3657 feet

Operator License No.: 34162
Op Name: NEW GULF OPERATING LLC
Address: 6310 E. 102ND ST.
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3650	2212	100 SX
SURF	8.625	230		270 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/20/2012 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-8088

Proposed Plugging Method: KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 06/20/2012 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3455' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2212' AND PULL TO 1050' AND PUMP 35 SX'S CEMENT. PULL CASING TO 600' AND PUMP 35 SX'S CEMENT. PULL CASING TO 280' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3534	3540	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-39774.

Plugged through: CSG

District: 02

Signed Virgil Clothier
7/18/12 (TECHNICIAN)

RECEIVED
JUL 10 2012
KCC WICHITA