

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21537-00-00
Spot: W2SESE Sec/Twnshp/Rge: 22-23S-10W
660 feet from S Section Line, 990 feet from E Section Line
Lease Name: HALLE Well #: 1
County: RENO Total Vertical Depth: 3770 feet

Operator License No.: 34162
Op Name: NEW GULF OPERATING LLC
Address: 6310 E. 102ND ST.
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3595		
PROD	5.5	3717		400 SX
SURF	10.75	216		280 SX
T1	2.875	3612		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/15/2012 4:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: _____

Proposed Plugging Method: AS PR KCC RULES & REGS

Plugging Proposal Received By: DAVID BOLLENBACK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/15/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3469' - CAPPED WITH 5 SX CEMENT. CUT CASING PIPE OFF @ 1350' SPOTTED 35 SX CEMENT. PULLED CASING TO 925' SPOTTED 35 SX CEMENT. PULLED CASING TO 260' CIRCULATED TO SURFACE WITH 175 SX CEMENT. PLUG FELL BACK 90'. 6/20/12 TOPPED WITH 10 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3635	3675		
3519	3526		

RECEIVED
JUL 10 2012
7-10-12
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX

Plugged through: CSG

District: 02

Signed B. J. Hope
7/18/12 (TECHNICIAN)

JK