

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15535-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 33-19S-12W  
4928 feet from S Section Line, 4892 feet from E Section Line  
Lease Name: JOHNSON AB Well #: 2  
County: BARTON Total Vertical Depth: 3393 feet

Operator License No.: 31528  
Op Name: MIKE KELSO OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3386		90 SX
SURF	8.625	150		150 SX

Well Type: EOR UIC Docket No: E23664.1 Date/Time to Plug: 06/20/2012 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL INC Phone: (620) 562-8088

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/20/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations sanded off. T/A well.  
Perforated at 1450' and 630'.  
Ran tubing to 3000'. Pumped 14 sx gel.  
Pulled tubing to 1450'. Circulated cement to surface on casing w/160 sx cement.  
Pulled tubing. Tied to casing. Pumped 182 sx cement.  
Tied to surface pipe. Pumped 10 sx cement pressured to 300 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3120	3340		

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed Bruce Rodie  
7/18/12 (TECHNICIAN)

CM

JUL 11 2012

to MIC 7/16/12

RECEIVED  
JUL 12 2012  
KCC WICHITA