

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15538-00-01
Spot: NWNENW Sec/Twnshp/Rge: 33-19S-12W
4921 feet from S Section Line, 3577 feet from E Section Line
Lease Name: JOHNSON AB Well #: 14
County: BARTON Total Vertical Depth: 3389 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3370		90 SX
SURF	8.625	160		150 SX

Well Type: EOR UIC Docket No: E23664.3 Date/Time to Plug: 06/19/2012 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL INC Phone: (620) 562-8088

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 06/19/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations sanded off. T/A well.
Perforated at 1450' and 630'.
Ran tubing to 3000'. Pumped 14 sx gel.
Pulled tubing to 1450'. Circulated cement to surface on casing w/200 sx cement w/300 # hulls.
Pulled tubing to 650'. Pumped 50 sx cement w/100 # hulls. Circulated out casing.
Tied to surface pipe. Pressured to 300 psi.
Checked 06/22/2012. Casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3153	3316		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
7/18/12 (TECHNICIAN) CM

cc to UIC 7/16/12

JUL 11 2012

RECEIVED
JUL 12 2012
KCC WICHITA