

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04293-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 35-18S-11W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ROBL Well #: 1  
County: BARTON Total Vertical Depth: 3368 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3365		
SURF	8.625	245		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2012 1:00 PM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO. Phone: (620) 587-3600

Proposed Plugging Method: Emergency plug rig over hole. Ran in tubing to 845'. Tubing stacked out. Tried to pull tubing back out of hole. Hung up on collars. Tubing might have run out of casing. Decided to plug.  
Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 845'. Pumped 50 sx cement.  
Pulled tubing to 535'. Pumped 175 sx cement w/400 # hulls. Circulated cement out casing and surface pipe.  
Pulled tubing. Topped off w/20 sx cement. Pressured to 150 psi.

Remarks: COPELAND ACID AND CEMENTING TICKET # 36395

Plugged through: CSG TBG

District: 04

Signed

Bruce Rodie  
7/18/12

(TECHNICIAN)

CM

RECEIVED  
JUL 12 2012  
KCC WICHITA

JUL 06 2012