

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04418-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 3-17S-11W
feet from Section Line, feet from Section Line
Lease Name: BURMEISTER F F Well #: 2
County: BARTON Total Vertical Depth: 3345 feet

Operator License No.: 6239
Op Name: ZINSZER OIL CO., INC.
Address: PO BOX 211
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3320		
SURF	10.75	310		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2012 12:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PERRY HERMAN Company: ZINSZER OIL Phone: (785) 625-9448

Proposed Plugging Method: Emergency Plug Rig over hole. Casing bad. Worked on well for 10 days.
Ordered 465 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2012 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500' and 750'.
Ran tubing to 2700'. Pumped 18 sx gel followed w/75 sx cement.
Pulled tubing to 1500'. Perforated out bottom of tubing. Pumped 125 sx cement.
Pulled tubing to 750'. Perforated out bottom of tubing. Pumped 100 sx cement.
Pulled tubing to 480'. Pumped 165 sx cement. Circulated cement out of casing. Pulled tubing.
Hole full.

Remarks: SWIFT SERVICES

Plugged through: ESG TBG

RECEIVED
JUL 12 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
7/18/12 (TECHNICIAN)

CM

JUL 11 2012