

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00231-00-00
Spot: SE Sec/Twnshp/Rge: 9-22S-32W
1355 feet from S Section Line, 1307 feet from E Section Line
Lease Name: ERICKSON L H GAS UNIT Well #: 1
County: FINNEY Total Vertical Depth: 2724 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2613		WITH 5 SX CMT
PROD	5.5	2718	638	WITH 600 SX CMT
SURF	8.625	527		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/20/2012 3:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2613' WITH 5 SX CMT. PLUG AT 2070' WITH 20 SX CMT. PLUG AT 1250' WITH 25 SX CMT. PLUG AT 650 CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2012 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2613' WITH 5 SX CMT. 1ST PLUG AT 2070' WITH 20 SX CMT. 2ND PLUG AT 1250' WITH 25 SX CMT. SHOOT CASING OFF AT 638' & TOO H. RUN TBG TO 650'. CIRCULATE WELL FULL OF CMT TO 0' USING 180 SX CMT. TOO H W/TBG & TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2663	2672		

RECEIVED
JUL 12 2012

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS A COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN)
7/18/12

RECEIVED
JUL - 5 2012
KCC DODGE CITY

[Handwritten mark]