

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-055-00241-00-00
 Spot: SE Sec/Twnshp/Rge: 17-22S-32W
1340 feet from S Section Line, 1431 feet from E Section Line
 Lease Name: HETT A Well #: 2
 County: FINNEY Total Vertical Depth: 2715 feet

Operator License No.: 32864
 Op Name: XTO ENERGY INC.
 Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1200		
CIBP		2460		WITH 5 SX CMT
PROD	5.5	2714	0	WITH 400 SX CMT
SURF	8.625	425		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/02/2012 11:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: LOAD HOLE W/ 9 PPG 36 VIS MUD. PUMP 240' CMT PLUG FROM 2450'-2690'. PULL UP HOLE 2030' & PUMP A 100' CMT PLUG FROM 1930'-2030'. CUT CASING @ FREEPOINT & LD CSG. PUMP A 100' CMT PLUG FROM 50' BELOW TO 50' ABOVE THE CUT OFF CASING. PULL UP HOLE TO 1200', LOAD HOLE W/ 9 PPG MUD. PUMP 200' CMT PLUG 1000' - 1200'. TOH TO 475' & PUMP A CMT PLUG FROM 4' - 475'. WELD ON ID MARKER. RESTORE LOCATION.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 07/05/2012 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2460' WITH 5 SX CMT. 7/2/12: PLUG AT 2030' WITH 25 SX CMT. NO CIRCULATION. TAG FL @ 300'. ATTEMPT TO LOAD HOLE. COULD NOT. SET CIBP @ 1200'. ATTEMPT TO LOAD HOLE. COULD NOT. RUN PACKER TO 630'. ATTEMPT TO LOAD TBG. COULD NOT. RUN PACKER TO 1170' & TESTED CIBP TO 500#. HAVE A HOLE IN 5 1/2" CASING BETWEEN 630' & 1170'. RUN BOND LOG FROM 1192' TO 300'. TOP OF CMT AT 660'. USABLE WATER COVERED. 7/3/12: RUN TBG TO 1200' & SPOT 55 SX CMT WITH HULLS. PERFORATE @ 455'. SDON. WAIT 3 HOURS. TAG TOC @ 1162'. RUN TBG TO 1130'. SPOT 55 SX CMT WITH 150# HULLS. HAD CIRCULATION UP 5 1/2" & 5 1/2" X 8 5/8" ANNULUS. SDON. 7/5/12: TAG TOC IN 5 1/2" CASING AT 692'. CIRCULATE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT FROM 455' TO 0' WITH 130 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2680	2684		
2669	2680		
2628	2646		
2510	2526		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED

JUL 12 2012

KCC WICHITA

District: 01

RECEIVED

JUL 10 2012

KCC DODGE CITY

Signed

[Handwritten Signature]
 7/18/12

(TECHNICIAN)