

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20790-00-00
Spot: SWNESE Sec/Twnshp/Rge: 29-25S-36W
1999 feet from S Section Line, 351 feet from E Section Line
Lease Name: LEE Well #: 1-29
County: KEARNY Total Vertical Depth: 5063 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4770		WITH 2 SX CMT
PROD	5.5	5063	0	WITH 250 SX CMT
SURF	8.625	1651		WITH 975 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2012 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4770' WITH 2 SX CMT. PLUG AT 1825' WITH 80 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 06/15/2012 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4770' WITH 2 SX CMT. PERFORATE @ 1825'. INJECTION RATE 3 BPM @ 400#. PUMP 80 SX CMT (40 SX OUT PERFS). LET SET. TEST TO 500#. HOLDING. PERFORATE @ 700'. CIRCULATE CMT TO SURFACE USING 250 SX CMT. 15 SX CMT TO THE PIT.

Perfs:

Top	Bot	Thru	Comments
4948	4953		
4819	4827		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

[Signature]
7/18/12

(TECHNICIAN)

RECEIVED
JUL - 5 2012
KCC DODGE CITY

RECEIVED
JUL 12 2012
KCC WICHITA

[Handwritten mark]