

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20911-00-00
Spot: NWSENW Sec/Twnshp/Rge: 20-10S-24W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: DAVE RUSH A Well #: 5
County: GRAHAM Total Vertical Depth: 4004 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4001		235 SX
SURF	8.625	264		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2012 10:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: CURTIS R LONGPINE Company: WESTERN WELL SERVICE Phone: (785) 625-0020

Proposed Perforations from 3938'-3944', 3770'-3774' and 3780'-3785'.
Plugging Shot perforations @ 2050'-1140'-255'.
Method: Squeezed @ 1826'-1857' w/250 sx cement.
Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/03/2012 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3136'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2500'. Pumped 100 sx cement.
Pulled tubing to 1088'. Pumped 60 sx cement w/50 # hulls. Good circulation of cement.
Pulled tubing out. Casing is full.
Tied on to back side. Squeezed w/30 sx cement. Hole standing full.

Remarks: SWIFT CEMENT CO TICKET # 21803 (AVEN WEAVERLING ON JOB)

Plugged through: TBG

RECEIVED
JUL 12 2012
KCC WICHITA

District: 04

Signed *Marvin Mills*
3/17/12 (TECHNICIAN)

CM

JUL 09 2012