

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00226-00-00
Spot: SW Sec/Twnshp/Rge: 5-22S-32W
1375 feet from S Section Line, 3940 feet from E Section Line
Lease Name: GREATHOUSE A Well #: 1-5
County: FINNEY Total Vertical Depth: 2726 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2600		WITH 5 SX CMT
PROD	5.5	2726	0	WITH 400 SX CMT
SURF	8.625	418		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/25/2012 2:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: LOAD HOLE W/ 9 PPG 36 VIS MUD, PUMP A 100' CEMENT PLUG FROM 2690' - 2590'. PUMP ANOTHER 100' CEMENT PLUG FROM 2040' - 1940'. CUT & PULL CSG AT FREEPOINT, PUMP A 100' CMT PLUG FROM 50' BELOW TO 50' ABOVE CSG STUB. PUMP A 200' CEMENT PLUG FROM 1200' - 1000'. PUMP 464' CEMENT PLUG FROM 468' 0 4' BELOW GROUND LEVEL. WELD ON ID PLATE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2012 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2600' WITH 5 SX CMT. 6/25/12: PUMP 30 SX CMT AT 2040'. SDON. 6/26/12: PRESSURE TEST CASING TO 500#. HOLDING. RAN BOND FROM 1850' TO 1050'. TOP OF GOOD CMT AT 1400'. SCATTERED CMT TO 1300'. PERFORATE AT 1160'. INJECTION RATE 2 1/2 BPM @ 100#. WELL STARTED CIRCULATING. PUMP 80 SX CMT VIA 5 1/2" CASING. DISPLACE WITH 24 BLS WATER. WELL SQUEEZED OFF TO 700# W/60 SX CMT (14 BBLs) OUT PERFS. HOLDING 300#. 20 SX CMT LEFT INSIDE CASING. AFTER 2 HOURS, TAG TOC IN 5 1/2" @ 1000'. PERFORATE AT 450'. CIRCULATE CMT TO SURFACE LEAVING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT USING 120 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2692	2695		
2681	2684		
2670	2673		
2652	2662		
2646	2649		
2630	2645		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

[Signature]
7/18/12

(TECHNICIAN)

RECEIVED
JUL - 5 2012
KCC DODGE CITY

RECEIVED
JUL 12 2012
KCC WICHITA

[Handwritten mark]