

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21364-00-00
Spot: SENE Sec/Twnshp/Rge: 17-22S-35W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: PINEGAR Well #: 1-17
County: KEARNY Total Vertical Depth: 4990 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4467		WITH 1 SX CMT
PROD	4.5	4989	1830	WITH 200 SX CMT
SURF	8.625	1655		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2012 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4490' WITH 2 SX CMT. PLUG AT 2100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1680' WITH 50 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 420' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2012 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4467' WITH 1 SX CMT. 1ST PLUG AT 2070' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 1677' WITH 50 SX CMT. 3RD PLUG AT 952' WITH 50 SX CMT. 4TH PLUG AT 416' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4542	4544		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
7/18/12

(TECHNICIAN)

RECEIVED

JUL - 3 2012

KCC DODGE CITY

RECEIVED

JUL 12 2012

KCC WICHITA