

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30213-00-01
Spot: SWNWNENE Sec/Twnshp/Rge: 28-14S-14W
4947 feet from S Section Line, 1069 feet from E Section Line
Lease Name: OLSON A J - B Well #: 4
County: RUSSELL Total Vertical Depth: 3284 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3100		
PROD	5.5	3200		275 SX
SURF	8.625	679		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2012 8:45 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: EMPIRE ENERGY E&P, LLC Phone: (620) 282-7893

Proposed Plugging Method: Ordered 400 sx of 60/40 pozmix 4% gel cement w/300 # hulls and 7 sx gel.
Perforations: 1400', 700' and 400'.
Knocked down CIB Plug @ 3100' to 3215'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/05/2012 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2943'. Pumped 7 sx of gel followed w/75 sx cement w/150 # hulls.
Pulled tubing to 1450'. Pumped 155 sx cement w/150 # hulls.
Cement circulated out the back side. Shut in the back side and pumped 70 sx cement to circulate the braden head.
POOH and topped off w/20 sx cement.

Perfs:

Top	Bot	Thru	Comments
3204	3225		
3134	3136		
3112	3114		
3054	3056		
3004	3006		

Remarks: QUALITY CEMENTING TICKET # 902

Plugged through: TBG

District: 04

Signed Ray A. Dinkel (TECHNICIAN)

CM

JUL 09 2012

RECEIVED
JUL 12 2012
KCC WICHITA