

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20806-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 19-18S-31W  
2183 feet from S Section Line, 4471 feet from E Section Line  
Lease Name: WIECHMAN Well #: 12-19-1831  
County: SCOTT Total Vertical Depth: 4794 feet

Operator License No.: 33476  
Op Name: FIML NATURAL RESOURCES, LLC  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2999		WITH 450 SX CMT
PROD	5.5	4790	0	WITH 740 SX CMT
SURF	8.625	368		WITH 240 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2012 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: EDDIE AMBERCROMBIE Company: FIML Phone: (785) 672-3452

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/27/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT & 150# HULLS TO 3906'. PUMP 28 BBL GEL SPACER BACK TO 2450'. PUMP 240 SX CMT FROM 2450' TO 0'. PRESSURE TO 1000#. HOLDING AT 700#. PUMP 5 SX CMT DOWN ANNULUS. PRESSURED TO 400#.

Perfs:

Top	Bot	Thru	Comments
4455	4457		
4209	4212		
4133	4138		
4004	4007		
3964	3967		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

JUL - 3 2012

KCC DODGE CITY

Signed

*[Signature]*  
3/17/12

(TECHNICIAN)

RECEIVED  
JUL 12 2012  
KCC WICHITA

*[Handwritten mark]*