

15-135-21511-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 29 Twp. 19S Rge. 25W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE NW SE


Lease Owner Strata Drilling Company
Lease Name French Well No. #1
Office Address P. O. Box 355, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole

Date Well completed September 17, 1978 19
Application for plugging filed September 17, 1978 19
Application for plugging approved September 17, 1978 19
Plugging commenced September 17, 1978 19
Plugging completed September 17, 1978 19
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane L. Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4592'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole plugged with 50-50 pozmix, 2% gel, as Follows: 70 sacks @ 900', 20 Sacks @ 240', hulls and 10 sacks @ 40', 2 sacks each in mousehole and rathole. Plugging completed at 7:15 p.m., September 17, 1978.

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1978
09-29-1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company


STATE OF Kansas COUNTY OF Barton, ss.
Kenneth J. Link (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Kenneth J. Link* President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1978.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.



D R I L L E R S L O G

#1 French

CASING RECORD: 8 jts. used 28# 8-5/8" surface casing	COMPANY: Strata Drilling Company	DESCRIPTION: NE NW SE Section 29-19S-25W Ness County, Kansas
TOTAL ROTARY DEPTH: 4592'	CONTRACTOR: Strata Drilling Company	ELEVATION: 2567' GL
	COMMENCED: September 9, 1978	
	COMPLETED: September 17, 1978	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale	0	305	Ran 291' used 28# 8-5/8" surface casing; set and cemented at 296' with 190 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 11:00 p.m., September 9, 1978.
Sand, shale	305	1827	
Anhydrite	1827	1867	
Shale	1867	1935	
Lime and shale	1935	3615	
Lime	3615	3835	
Lime and shale	3835	4028	Ran 3 drill stem tests.
Lime	4028	4385	Hole plugged with 50-50 pozmix, 2% gel, as follows: 70 sacks @ 900', 20 sacks @ 240', hulls and 10 sacks @ 40', 2 sacks each in mousehole and rathole. Plugging completed at 7:15 p.m., September 17, 1978.
Lime and Shale	4385	4592	

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Sworn to and subscribed before me this 28th day of September, 1978.

My appointment expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1978
09-29-1978
CONSERVATION DIVISION
Wichita, Kansas

