

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-20349-00-00

LEASE NAME Schlegel #2

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NW NE

SEC. 29 TWP. 19s RGE. 25w (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/6/85

Plugging Completed 9/18/85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Co.

ADDRESS 6733 S. Yale, Box 21468, Tulsa, Ok. 74121

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well \_\_\_\_\_  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4634'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	411'	none
				5 1/2"	4624'	1809'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Plugged bottom with sand to 4475' & 5 sacks cement. Shot pipe at 3040', 2837', 2634', 2430', 2226', 2023', & 1809'. Pulled 54 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 15 gel, 1 hull, plug, & 200 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
 Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1985

My Commission expires:



Irene Hoover  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 30 1985  
 09-30-1985  
 CONSERVATION DIVISION  
 Wichita, Kansas

*Prod -  
Great Bend*

15-135-20349-00-00  
GEOLOGIC LOG  
LITHOLOGY and DRILLING TIME



COMPANY <u>LEBEN</u>	ELECTRIC LOGS <u>LATERAL LOG</u>
	<u>GAMMA RAY NEUTRON</u>
	<u>SCHLUMBERGER</u>
WELL <u>SCHLEGEL #2</u>	PRODUCTION _____
FIELD <u>SPRUILL</u>	
LOCATION <u>CEN NW 1/4 NE 1/4</u>	
SECTION <u>29</u> TWP <u>19S</u> RNG <u>25W</u>	
COUNTY <u>NESS</u>	ELEVATION
STATE <u>KANSAS</u>	KB <u>2617</u>
	DF _____
	GL <u>2612</u>

CONTRACTOR <u>LEBEN DRILLING INC.</u>	CASING RECORD:
SPUD <u>JUNE 4 1970</u> COMPLETED <u>JUNE 14 1970</u>	SURFACE <u>8 1/2" @ 11 W / 250 SX</u>
DEPTHS MEASURED FROM: DRILLING <u>4634</u> LOG <u>4636</u>	<u>5 1/2" @ 4624</u>
	PRODUCTION _____

STRATIGRAPHIC MARKERS and STRUCTURAL RELATIONSHIP \*

MARKER	SAMPLE	ELECTRIC LOG	DATUM (Sea Level)	STRUCTURAL POSITION
ANHYDRITE		1882	735	+2
HEBNER	3953	3955	-1338	-5
LANSING KC.	3994	3976	-1379	-4
BASF. KC.	4360	4359	-1742	+1
FT. SCOTT	4515	4515	-1898	-9
CHENOCKEE	4563	4558	-1941	+6
WEATHERED MISS	4610	4608	-1991	-2
MISSISSIPPI	4622	4622	-2005	-7
TOTAL DEPTH		4634 4636	-2017	+1

\* Referred to: SCHLEGEL #1 *Geo. Wanto*

15-135-20349-00-00

Sec. 29 T. 19 R. 25

Company Leben Drilling, Inc.  
Contractor Leben Drilling, Inc.  
Farm Schlegel #2  
Total Depth 4634' RTD  
Commenced 6-4-70  
Completed 6-15-70

Loc. C NW NE

County Ness

Casing 8 5/8" 20# New Casing set @ 411.3'  
w/250 sxs. Common 2% C.C. 2% Gel

Production  
Producer


Figures Indicate Bottom of Formations

20	Top Soil
80	Post Rock
1799	Shale
1879	Shale & Shells
1919	Anhydrite
2850	Lime & Shale
3050	Lime
4080	Lime & Shale
4182	Lime
4225	Lime & Shale
4565	Lime
4604	Lime & Chert
4619	Sand
4634	Mississippi
<u>4634</u>	<u>RTD</u>

RECEIVED  
STATE CORPORATION COMMISSION

JUN 27 1970

CONSERVATION DIVISION  
Wichita, Kansas

06-27-1970

State of Kansas  
County of Barton SS

I, James R. Rodgers of Leben Drilling, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the Schlegel #2 Well.

*James R. Rodgers*

Subscribed and sworn to before me this 19th day of June, 1970

My Commission Expires:  
November 13, 1973