


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 28 Twp. 19S Rge. 25 ~~XXXXXX~~ (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner M. P. Gilbert
Lease Name Schlegel Well No. 1
Office Address 2133 S. Bel Aire, Room 9, Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 10 1964
Application for plugging filed December 10 1964
Application for plugging approved December 10 1964
Plugging commenced December 10 1964
Plugging completed December 10 1964
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4673 RTD Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Shale & Clay	0	165	8 5/8"	140'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 180' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1964
12-16-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Bldg., Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Dan J. Kornfeld contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth Natl. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of December 1964

My commission expires September 14, 1968

Sandra Kay Peer
Sandra Kay Peer Notary Public.



LOG

15-135-00310 00 00

COMPANY: M. P. Gilbert
 CONTRACTOR: Empire Drilling Company
 FARM: Schlegel #1
 LOCATION: C SW NW Section 28-19S-25W, Ness County, Kansas
 COMMENCED: November 26, 1964
 COMPLETED: December 10, 1964
 ELEVATION: 2546 KB
 POTENTIAL: D & A

0	to	165	Surface - Clay & Shale
165	to	1020	Shale
1020	to	1203	Sand & Shale
1203	to	1216	Blaine Anhydrite
1216	to	1545	Shale & Red Bed & Sand
1545	to	1810	Shale & Shells
1810	to	2150	Shale
2150	to	2815	Lime & Shale
2815	to	2920	Lime
2920	to	3685	Shale - Lime
3685	to	3764	Lime
3764	to	3845	Lime & Shale
3845	to	3945	Chalky Lime & Shale
3945	to	3990	Lime
3990	to	4080	Lime & Shale
4080	to	4175	Cherty Lime
4175	to	4218	Lime
4218	to	4270	Lime - Shale
4270	to	4415	Lime
4415	to	4545	Lime & Shale
4545	to	4570	Conglomerate
4570	to	4645	Mississippi Dolomite & Chert
4645	to	4673	Mississippi Osage
4673			Rotary Total Depth

SET: 140' of 8 5/8" with 60 sacks cement.

WELEX ELECTRIC LOG TOPS:

Heebner	3888	-1342
Toronto	3909	-1363
Lansing	3932	-1386
Base Kansas City	4290	-1744
Fort Scott	4380	-1834
Cherokee	4438	-1892
Conglomerate	4531	-1985
Mississippi	4556	-2010
Mississippi Solid	4574	-2028
Mississippi Osage	4653	-2107
Log Total Depth	4673	

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1964
12-16-1964
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Schlegel #1, C SW NW Section 28-19S-25W, Ness County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 15th day of December, 1964.

Sandra Kay Peer
Sandra Kay Peer, Notary Public



My commission expires September 14, 1968.