



15-135-20246-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 05-14-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Leben Drlg. has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Leben & McClure

Complete Address: 815 Wichita Plaza Wichita, Ks.

Lease Name: Schegel Well No. 1

Location: C SE SE Sec. 3 Twp. 19 Rge. (E)(W) 25

County: Ness Total Depth 4443 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 390' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 172 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with
2 sk cmt.

Very truly yours,

Leo F. Murray
 Conservation Division Agent