

State of Kansas



15-135-20879-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1974
04-25-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mason of Dunne-Gardner Petro., Inc. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg., Co.

Complete Address: 617 Union Center, Wichita, Ks.

Lease Name: Di Spirito Well No. 1

Location: SE NW NE Sec. 31 Twp. 19 Rge. (E)(W) 25

County: Ness Total Depth 4680' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Mason was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680' and displace
70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messing
Conservation Division Agent