

PRODUCTIVITY TEST BARREL TEST

* RULE 82-3-202 of the General Rules and Regulations of the State of Kansas:

Productivities, when to be taken. (f) Pool tests. Pool tests shall be taken as ordered by the Commission at twelve month intervals thereafter.

COUNTY Ness
FIELD McDonald NE
PRODUCING FORMATION Marm.
OPERATOR Palomino Pet.
LEASE Stanley

EFFECTIVE DATE SEP 1 1987
(Office use only)
PURCHASER Clear Creek
ADDRESS _____
(if new operator)

* WELL NO.	SEC.	TWP.	RGE.	BOPD	WATER %	DATE TAKEN
1. <u>1</u>	<u>27</u>	<u>18</u>	<u>24 W</u>	<u>160</u>	<u>NONE</u>	<u>9-16-87</u>
2.	_____	_____	_____	_____	_____	_____
3.	_____	_____	_____	_____	_____	_____
4.	_____	_____	_____	_____	_____	_____
5.	_____	_____	_____	_____	_____	_____
6.	_____	_____	_____	_____	_____	_____
7.	_____	_____	_____	_____	_____	_____
8.	_____	_____	_____	_____	_____	_____
9.	_____	_____	_____	_____	_____	_____
10.	_____	_____	_____	_____	_____	_____

FIELDMAN'S REMARKS: _____

WITNESSES:
Dan Godwin FOR STATE
Sam Bruntz FOR OPERATOR
_____ FOR OFFSET

*NOTE: IF THE WELL IS TEMPORARILY ABANDONED AT TIME OF TEST, BUT AT A LATER DATE IS PUT ON PUMP, PLEASE HAVE IT TESTED AT THAT TIME. THIS PREVENTS OVERPRODUCTION ON THE TABLE "B" REPORT. TO SCHEDULE A TEST CALL THE DISTRICT OFFICE IN THE AREA IN WHICH THE WELL IS LOCATED.

STATE CORPORATION COMMISSION OF KANSAS.
STATE CORPORATION COMMISSION

CONSERVATION DIVISION

SEP 21 1987

CONSERVATION DIVISION
Wichita, Kansas

1. Copy for Sam Brantz
2. ✓ ✓ Don Goodrow

PALOMINO PETROLEUM₃

ROUTE 5, BOX 51-C
NEWTON, KANSAS 67114

file in well file.

R. W. WATCHOUS
OWNER - GEOLOGIST

(316) 283-0232

Info. for State Test: #1 Stanley

150' S. of C SW SW

Sec 27-18-24W

Ness County, KS

API # 15-135-23152

McDonald NE

T.D.: 4305

SPUDDED 8-26-87

P.B.T.D.: 4287

P.O.P. 9-11-87

Surface: set 211' of 8⁵/₈" cemented w/ 140 sacks (cir.)

Oil String: 4300' of 5¹/₂" cemented with 250 sacks 60.40 Pozmix
2% gel, 10% Salt; 15 Bbl salt flush.

Alternate 2: Cemented down backside w/ 350 sacks 50-50 Pozmix 6% gel.
Trouble w/ temperature survey - didn't record until 1600'
but indicated good cement from 1600' to surface

Completion: Bridge Plug set at 4287'
Prof. Marmaton 4075-4084 3/ft SSB

No Acid - P.O.P. 9-11-87

2³/₈" O.D. tubing set at 4283'

pump size = 2" x 1¹/₂" x 12' 13³/₄ strokes per minute 46" stroke

Oil gravity = 40°

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1987

CONSERVATION DIVISION
Wichita, Kansas.

9-15-87