

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22913-00-00

Spot: NWSESE

Sec/Twnshp/Rge: 21-16S-12W

990 feet from S Section Line,

990 feet from E Section Line

Lease Name: STOSKOPF B

Well #: 7

County: BARTON

Total Vertical Depth: 3393 feet

Operator License No.: 9390

Op Name: SCHREIBER, MARY ANN DBA SCHREI

Address: 598 2ND AVE

CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3384		125 SX
SURF	8.625	452		250 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/03/2012 12:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICK SCHREIBER

Company: SCHREIBER OIL

Phone: (620) 793-2032

Proposed Plugging Method: Packer stuck in well at 1207'. Will plug.
Ordered 500 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/03/2012 12:00 AM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran perf gun through tubing to 1315' and perforated.
Tied to tubing. Pumped 250 sx cement. Ran three point un threaded tubing. Pulled to 845' and perforated. Pulled to 450' and perforated. Ran tubing back to 845'. Pumped 125 sx cement. Pulled tubing to 450'. Circulated cement to surface on casing w/50 sx cement. Shut in casing. Circulated cement to surface on surface pipe w/150 sx cement. Pulled tubing. Topped off w/5 sx cement.

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG T B6

RECEIVED
JUL 12 2012
KCC WICHITA

District: 04

Signed

Bruce Rodie
7/18/12

(TECHNICIAN)

CM

JUL 06 2012