

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22515-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 17-18S-15W
2970 feet from N Section Line, 4950 feet from E Section Line
Lease Name: BAHR Well #: 1
County: BARTON Total Vertical Depth: 3558 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3558		475 SX
SURF	8.625	867		450 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/09/2012 8:30 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: MIKE Company: LD DRILLING Phone: (620) 793-7237

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/200 # hulls.
Perforations: 1550', 860' and 250'.
PBTB: 1960'.
Production perforations: 1838' - 1846' and 1850' - 1858'.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2012 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1800'. Pumped 50 sx cement w/100 # hulls.
Pulled tubing to 960'. Pumped 60 sx cement.
Cement circulated out of backside.
Shut in backside valve and pumped additional 100 sx cement.
Cement circulated out braden head.
POOH. Topped off w/10 sx cement. Shut in casing and braden head.

Perfs:

Top	Bot	Thru	Comments
1850	1858		
1838	1846		

Remarks: COPELAND ACID AND CEMENTING TICKET # 39182

Plugged through: TBG

RECEIVED
JUL 16 2012
KCC WICHITA

District: 04

Signed

Ray Dinkel
7/26/12

(TECHNICIAN)

CM

JUL 10 2012