

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23277-00-00
Spot: NENENWNE Sec/Twnshp/Rge: 33-33S-8E
5156 feet from S Section Line, 1595 feet from E Section Line
Lease Name: DUDGEON Well #: 1
County: COWLEY Total Vertical Depth: 2349 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2349		440 SX
SURF	8.625	50		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2012 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND OFF & CAP W/4 SXS, TAG ABOVE 2265', CIRC TOP PLUG 500'-0'.

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 06/20/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK ABOVE PERFS @ 2270', DUMP BAILED 4 SXS CEMENT ON TOP. RIH W/3-4" TBG ON BACKSIDE OF 4-1/2" CASING @135', RIH W/2" TBG ON INSIDE OF 4-1/2" CASING @ 500'. 6-20-2012, CONSOLIDATED OIL WELL SERVICES, HOOKED UP TO 3/4" TBG, ESTABLISHED CIRCULATION, & MIXED PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN 3/4" TBG. HOOKED UP TO 2" TBG, CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED PUMPED 42 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE 5:00 PM 6-20-2012, CONSOLIDATED CEMENT TICKET #36205.

Perfs:

Top	Bot	Thru	Comments
2314	2320	CSG	

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
7/26/12 (TECHNICIAN)

RECEIVED
JUL 18 2012
KCC WICHITA