

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23357-00-00  
Spot: SESWNWNE Sec/Twnshp/Rge: 33-33S-8E  
4160 feet from S Section Line, 1998 feet from E Section Line  
Lease Name: DUDGEON Well #: 3-C  
County: COWLEY Total Vertical Depth: 2370 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2370		500 SX
SURF	8.625	50		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2012 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND OFF & CAP W/4 SXS, TAG ABOVE 2250', CIRC TOP PLUG 500'-0'.

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/20/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK ABOVE PERFS @ 2259', DUMP BAILED 4 SXS CEMENT ON TOP. RIH W/2" TBG ON INSIDE OF 4-1/2" CASING @ 500'. CONSOLIDATED OIL WELL SERVICES, ESTABLISHED CIRCULATION, MIXED & PUMPED 56 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE 5:00 PM 6-20-2012, CONSOLIDATED CEMENT TICKET #36209.

Perfs:

Top	Bot	Thru	Comments
2301	2309	CSG	

Remarks: CEMENT @ SURFACE ON BACKSIDE OF 4-1/2" CASING.

Plugged through: TBG

District: 02

Signed Duane Krueger  
7/18/12 (TECHNICIAN)

RECEIVED

JUL 18 2012

KCC WICHITA