

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23779-00-027
Spot: NESWSE Sec/Twnshp/Rge: 4-31S-6E
1258 feet from S Section Line, 1415 feet from E Section Line
Lease Name: DRAKE Well #: A-2
County: COWLEY Total Vertical Depth: 3300 feet

Operator License No.: 9913
Op Name: BULLSEYE PETROLEUM, INC.
Address: 15820 PLYMOUTH RD
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3251		
PROD	5.5	3298	1424	75 SX
SURF	8.625	310		225 SX

Well Type: SWD UIC Docket No: D27039.0 Date/Time to Plug: 06/22/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND BACK TO 3200', W/5 SXS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERF @ 3200', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5-1/2" CASING @ 1424', LAYED DOWN CASING TO 374', SWEDGED IN COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. FINISHED LAYING DOWN CASING. TOPPED WELL BACK TO SURFACE W/CEMENT. P & A COMPLETE 6-25-2012, 5:00 PM. COPELAND CEMENT TICKET #39781.

Perfs:

Top	Bot	Thru	Comments
3250	3254	CSG	

Remarks: COMPLIANCE / TA

Plugged through: CSG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)
cc to UIC 7/19/12
7/26/12

RECEIVED

JUL 18 2012

KCC WICHITA