

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20741-00-01
Spot: SWNENENW Sec/Twnshp/Rge: 13-21S-35W
4627 feet from S Section Line, 3226 feet from E Section Line
Lease Name: SCOTT Well #: 2-13
County: KEARNY Total Vertical Depth: 5000 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY DR STE350
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3200		WITH 2 SX CMT
DVT		3208		
PROD	4.5	4997	0	WITH 400 SX CMT
SURF	8.625	630		WITH 400 SX CMT

Well Type: EOR UIC Docket No: E30071.11 Date/Time to Plug: 07/03/2012 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GORDON Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: SET CIBP @ 3800' WITH 2 SX CMT. PLUG AT 2000' WITH 10 SX GEL & 25 SX CMT. PLUG AT 1100' WITH 25 SX CMT. PLUG AT 630' WITH 25 SX CMT. PLUG AT 60' CIRCULATE TO SURFACE. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: PARTIAL
Date/Time Plugging Completed: 07/03/2012 11:30 AM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP@ 3200' WITH 2 SX CMT ON TOP. COULD NOT GET DOWN HOLE ANY FARTHER. 1ST PLUG AT 212' WITH 10 SX GEL & 25 SX CMT. 2ND PLUG AT 1105' WITH 25 SX CMT. 3RD PLUG AT 630' CIRCULATE CMT TO SURFACE WITH 50 SX CMT. CHECK BACKSIDE WITH CMT, TOOK 75 SX.

Perfs:

Top	Bot	Thru	Comments
4866	4878		
4840	4850		

RECEIVED
JUL 19 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Daniel Bernasconi
7/26/12 (TECHNICIAN)