

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-30099-00-00
Spot: NWSE Sec/Twnshp/Rge: 33-27S-20W
2205 feet from S Section Line, 1886 feet from E Section Line
Lease Name: BRENSING I Well #: 1
County: KIOWA Total Vertical Depth: 4911 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 4900 | 1350 | WITH 125 SX CMT |
| SURF | 8.625 | 265 | | WITH 275 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND OPEN HOLE & PLACE 5 SX CMT ON TOP. PLUG AT 1330' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2012 4:15 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SANDED TO 4855' WITH 4 SX CMT ON TOP. 1ST PLUG AT 1335' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 30' WITH 35 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4893 | 4896 | | |

RECEIVED
JUL 19 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed Daniel Bernasconi
7/10/12 (TECHNICIAN)

RECEIVED
JUL 10 2012
KCC DODGE CITY

Handwritten initials