

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21988-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 30-30S-31W
1625 feet from N Section Line, 1270 feet from E Section Line
Lease Name: FITZGERALD 'A' Well #: 3-30
County: HASKELL Total Vertical Depth: 4810 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4500		WITH 2 SX CMT
CIBP		4650		
PROD	4.5	4802	2516	150 SX
SURF	8.625	1819		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2012 1:00 PM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: CALVIN MIKKELSON Company: MCCOY PETROLEUM Phone: (620) 272-7058

Proposed Plugging Method: SET CIBP @ 4500' WITH 2 SX CMT. PLUG AT 1860' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 06/27/2012 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TOC @ 3600' PER CBL SET CIBP @ 4500' WITH 2 SX CMT. SHOT CASING AT 3400', UNABLE TO PULL. RESHOT CASING @ 2516'. 1ST PLUG AT 1860' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4686	4689		
4518	4524		

RECEIVED
JUL 19 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JUL - 3 2012
KCC DODGE CITY

Signed Jack MacLasky
7/26/12 (TECHNICIAN)

any