

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21810-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 33-21S-24W
2000 feet from N Section Line, 335 feet from W Section Line
Lease Name: JAMES SOREM Well #: 1-33
County: HODGEMAN Total Vertical Depth: 4692 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/10/2012 11:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 07/10/2012 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED
JUL 19 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren
07/26/12 (TECHNICIAN)

RECEIVED

JUL 10 2012 RP

KCC DODGE CITY

AMR