

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20436-00-00  
Spot: SENESE Sec/Twnshp/Rge: 5-33S-19W  
1667 feet from S Section Line, 327 feet from E Section Line  
Lease Name: BAYNE Well #: 2-5  
County: COMANCHE Total Vertical Depth: 5321 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5070		WITH 2 SX CMT
PROD	4.5	5319	2400	WITH 250 SX CMT
SURF	8.625	646		WITH 500 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2012 9:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: CIBP @ 5070' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 30' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2012 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 5070' WITH 2 SX CMT. HAD TO WASH DOWN TBG TO GET TO 819' & DIDN'T WANT TO GET STUCK. 1ST PLUG AT 819' WITH 200# HULLS, 15 SX GEL & 50 SX CMT. 2ND PLUG AT 664' WITH 50 SX CMT. 3RD PLUG AT 261' WITH 40 SX CMT. 4TH PLUG AT 58' WITH 35 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5112	5224		MISSISSIPI

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED  
JUL 16 2012  
KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)  
RECEIVED  
JUL 23 2012  
KCC WICHITA

AWZ