

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22294-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 13-31S-35W
1250 feet from S Section Line, 100 feet from W Section Line
Lease Name: MOORHEAD Well #: 3-13A
County: STEVENS Total Vertical Depth: 3150 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2880		WITH 5 SX CMT
PROD	5.5	3150	0	WITH 340 SX CMT
SURF	8.625	638		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/12/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2880' & 5 SX CMT. PLUG AT 1790' WITH 80 SX CMT. WOC & TAG TOC. FILL 5 1/2" CASING TO SURFACE & CHECK ANNULAR SPACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 07/13/2012 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 2880' WITH 5 SX CMT. PUMPED 80 SX CMT & 100# HULLS @ 1790'. SDON. TAGGED TOC @ 1295'. FILLED 5 1/2" CASING WITH 80 SX CMT. PUMPED 40 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2914	2928		
2908	2911		
2887	2890		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
7/16/12 (TECHNICIAN)

RECEIVED
JUL 19 2012
KCC DODGE CITY

RECEIVED
JUL 23 2012
KCC WICHITA

PNY