

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21605-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 17-25S-16W
990 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SETTE Well #: A #6
County: EDWARDS Total Vertical Depth: 4550 feet

Operator License No.: 31000
Op Name: PRATER OIL & GAS OPERATIONS, INC.
Address: 906 WILLIAM WAY
PRATT, KS 67124

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 312 | | |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/11/2012 3:00 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: LARRY Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 07/11/2012 5:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

District: 01

RECEIVED
JUL 18 2012
KCC DODGE CITY

Signed Ken Jehlik
RECEIVED 7/23/12 (TECHNICIAN)
JUL 23 2012
KCC WICHITA

Handwritten initials