



15-135-20471-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1971
CONSERVATION DIVISION
Wichita, Kansas

09-14-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of Lebem Drlg. has this

date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Lebem Drilling, Inc.

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: Antenem Well No. 1

Location: C E/2 NW SE Sec. 23 Twp. 19 Rge. (E)(W) 21

County: Ness Total Depth 4480' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Delaney was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sk cmt thru drill pipe. Heavy mud to 360' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,

1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent