

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

RECEIVED

Form ACO-1
September 1999
Form Must Be Typed

JAN 24 2003

KCC WICHITA ORIGINAL

Operator: License # 30537
Name: VENTURE RESOURCES, INC.
Address: P.O. Box 101234
City/State/Zip: Denver, CO 80250
Purchaser: NCRA
Operator Contact Person: Ronald T. Mackey
Phone: (303) 722-2899
Contractor: Name: Discovery Drilling CO., Inc.
License: 31548
Wellsite Geologist: Ron & Greg Mackey

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>12/05/02</u>	<u>12/09/02</u>	<u>12/21/02</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 051-25,174-00-00
County: Ellis
SE NE NE Sec. 14 Twp. 11 S. R. 18 East West
990 feet from S / (circle one) Line of Section
330 feet from (circle one) W Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Deane Well #: 5
Field Name: Bemis-Shutts
Producing Formation: Arbuckle
Elevation: Ground: 1858 Kelly Bushing: 1866
Total Depth: 3410 Plug Back Total Depth: 3387
Amount of Surface Pipe Set and Cemented at 220.89 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 1757/kb Feet
If Alternate II completion, cement circulated from 1757
feet depth to Surface w/ 480 sx cmt.

Drilling Fluid Management Plan File 11 Dec 1.30.03
(Data must be collected from the Reserve Pit)
Chloride content 14,000 ppm Fluid volume 240 bbls
Dewatering method used Haul free fluid
Location of fluid disposal if hauled offsite: _____
Operator Name: Venture Resources, Inc.
Lease Name: E.Ridler(Burnett)#1 License No.: 30537
Quarter NW Sec. 12 Twp. 11 S. R. 18 East West
County: Ellis Docket No.: D 01,764


INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: PRESIDENT Date: 1-9-03

Subscribed and sworn to before me this 9TH day of January

Notary Public
Date of Commission Expires: _____
Linda G. Mackey
Notary Public State Of Colorado
My Commission Expires: 9/21/2006



KCC Office Use ONLY

Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
 ORIGINAL JAN 24 2003
 KCC WICHITA

Operator Name: VENTURE RESOURCES, INC. Lease Name: Deane Well #: 5
 Sec. 14 Twp. 11 S. R. 18 East West County: Ellis

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Anhydrite	1120	+746
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Topeka	2801	-935
List All E. Logs Run:		Heebner	3024	-1158
Dual Induction, Dual Compensated Porosity, Sonic Cement Bond Log		LKC	3066	-1200
		Arbuckle	3350	-1484

CASING RECORD							
New				Used			
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface Pipe	12 1/4"	8 5/8"	20	220.89	Common	150	2%Gel&3%CC
Production	7 7/8"	5 1/2"	14	3411	ASC	175	2%Gel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input checked="" type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	Sur/1757	60/40	480	6% Gel ,Floreal, 75#

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used)	
4/ft	3353-3359		NONE	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2 7/8	3348	None	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Date of First, Resumed Production, SWD or Enhr.		Producing Method			
12/21/02		Flowing <input type="checkbox"/> Pumping <input checked="" type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) <input type="checkbox"/>			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	35		80		30

Disposition of Gas: Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

(If vented, Submit ACO-18.)

ORIGINAL

VENTURE RESOURCES, INC.

DST REPORT
DEANE #5RECEIVED
JAN 24 2003
KCC WICHITADST #1 LANSING

INTERVAL: 3092 ft (KB) to 3132 ft (KB)
 TIMES: Open 15min, Shut in 30 min, Open 45 min, Shut in 75 min.
 TEST COMMENT: Strong blow, BOB 10 min. 1st open
 Strong blow, BOB 11 min. 2nd open

RECOVERY: 35 ft Oil stain mud, 360 ft gas in pipe
 SAMPLER: 800 ML GAS, 40 ML OIL, 2960 ML MUD, 200 ML WATER @ 100 PSI

PRESSURES: Flow: 43-54 psi, Shut-in: 145-148 psi. Hrdo-static: 1513-1491 psi.

DST #2 SIMPSON SD/ UPPER ARBUCKLE

INTERVAL: 3340 ft (KB) to 3359 ft (KB)
 TIMES: Open 15 min, Shut in 30 min, Open 20 min, Shut in 30 min.
 TEST COMMENT: Strong blow, BOB 1 min. 1st open
 Strong blow, BOB 1 min. 2nd open

RECOVERY: 1580 ft Gassy oil- 10% gas, 90% oil
 SAMPLER: 4000 ML OIL, NO WATER

PRESSURES: Flow: 509-714 psi. Shut-in: 1069-1069 psi. Hrdo-static: 1644-1699 psi.

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

15051251740000

*** INVOICE ***

Invoice Number: 088739

ORIGINAL

Invoice Date: 12/13/02

RECEIVED

JAN 24 2003

KCC WICHITA

Sold Venture Resources Co.
 To: P. O. Box 101234
 Denver, CO
 80250-1234

Cust. I. D.: Vent
 P.O. Number...: Deane #5
 P.O. Date....: 12/13/02

Due Date: 01/12/03
 Terms: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	150.00	SKS	6.6500	997.50	E
Gel	3.00	SKS	10.0000	30.00	E
Chloride	5.00	SKS	30.0000	150.00	E
Handling	150.00	SKS	1.1000	165.00	E
Mileage (20) 150 sks @\$.04 per sk per mi	20.00	MILE	6.0000	120.00	E
Surface	1.00	JOB	520.0000	520.00	E
Mileage pmp trk	20.00	MILE	3.0000	60.00	E
Plug	1.00	EACH	45.0000	45.00	E

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ 208.75
 ONLY if paid within 30 days from Invoice Date

Subtotal: 2087.50
 Tax: 0.00
 Payments: 0.00
 Total: 2087.50

*SURFACE
 CEMENT*

75518

\$ 1,878.80

ALLIED CEMENTING CO., INC.

15.051-25174-0000

10561

ORIGINAL

Federal Tax I.D. #

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE 12-5-02	SEC. 14	TWP. 11	RANGE 18	CALLED OUT Noon	ON LOCATION 2:30 PM	JOB START 4:30 PM	JOB FINISH 6:00 AM
LEASE DEANE	WELL# #5	LOCATION Hays N F RIVER		COUNTY Ellis	STATE KANSAS		
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Discovery Dols

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4 T.D. 222

CASING SIZE 8 5/8 DEPTH 221

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. 10'

PERFS. _____

DISPLACEMENT _____

OWNER SAME

CEMENT AMOUNT ORDERED 150 SKS Common

39.00, 2% GEL

COMMON	150	@	6.65	997.50
POZMIX		@		
GEL	3	@	10.00	30.00
CHLORIDE	5	@	30.00	150.00
		@		
		@		
		@		
		@		
		@		
HANDLING	150	@	1.10	165.00
MILEAGE	44/SK	@	2.70	120.00

EQUIPMENT

PUMP TRUCK CEMENTER R. DAVIS

221 HELPER _____

BULK TRUCK DRIVER GLEN

202 DRIVER _____

BULK TRUCK DRIVER _____

JAN 24 2003

KCC WICHITA SERVICE

TOTAL 1462.50

REMARKS:

CHARGE TO: VENTURE RESOURCES

STREET _____

CITY _____ STATE _____ ZIP _____

DEPTH OF JOB			
PUMP TRUCK CHARGE			520.00
EXTRA FOOTAGE		@	
MILEAGE	20	@	3.00
PLUG	8 5/8 SURF	@	45.00
		@	
		@	
TOTAL			625.00

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		
TOTAL			

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas AL

Thomas ALM
PRINTED NAME

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS. 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

1505125174 0600

* I N V O I C E *

ORIGINAL

Invoice Number: 088803

Invoice Date: 12/19/02

RECEIVED

JAN 24 2003

KCC WICHITA

Sold Venture Resources Co.
 To: P. O. Box 101234
 Denver, CO
 80250-1234

Cust. I.D.....: Vent
 P.O. Number...: Deane #5
 P.O. Date.....: 12/19/02
 Due Date...: 01/18/03
 Terms.....: Net 30

Item I.D./Desc	Qty	Used	Unit	Price	Net	TX
ASC	175.00		SKS	8.5000	1487.50	E
Gel	3.00		SKS	10.0000	30.00	E
WFR-2	500.00		GAL	1.0000	500.00	E
Handling	175.00		SKS	1.1000	192.50	E
Mileage (20)	20.00		MILE	7.0000	140.00	E
175 sks @\$.04 per sk per mi						
Production String	1.00		JOB	1130.0000	1130.00	E
Mileage pmp trk	20.00		MILE	3.0000	60.00	E
Plug	1.00		EACH	50.0000	50.00	E
Guide Shoe	1.00		EACH	150.0000	150.00	E
Insert	1.00		EACH	235.0000	235.00	E
Centralizers	6.00		EACH	40.0000	240.00	E
Basket	1.00		EACH	142.0000	142.00	E
Port Collar	1.00		EACH	1500.0000	1500.00	E

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ 585.70
 ONLY if paid within 30 days from Invoice Date

Subtotal: 5857.00
 Tax.....: 0.00
 Payments: 0.00
 Total....: 5857.00

*FIRST STAGE
 Port collar*

ALLIED CEMENTING CO., INC.

15-051-25174-0600

11517

ORIGINAL

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>12-10-02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>1:00PM</u>	JOB START <u>3:45PM</u>	JOB FINISH <u>4:00PM</u>
LEASE <u>DEANE</u>	WELL # <u>5</u>	LOCATION <u>HAYS N TO R. ROAD 1E</u>		COUNTY <u>ELIOT</u>	STATE <u>KS</u>		
OLD OR <u>NEW</u> (Circle one)				<u>S.S.</u>			

CONTRACTOR DISCOVERY

TYPE OF JOB PRODUCTION STRING

HOLE SIZE 7 7/8 T.D. 3410

CASING SIZE 5 1/2 DEPTH 3411

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 18"

CEMENT LEFT IN CSG. 18"

PERFS.

DISPLACEMENT 83 1/4

OWNER

CEMENT

AMOUNT ORDERED 175 ASC 2 1/2 GEL
500 GAL WFR-2

COMMON	<u>175 ASC @ 8⁵⁰</u>	<u>1487⁵⁰</u>
POZMIX	@	
GEL	<u>3 @ 10⁰⁰</u>	<u>30⁰⁰</u>
CHLORIDE	@	
WFR-2	<u>500gals @ 1⁰⁰</u>	<u>500⁰⁰</u>
	@	
	@	
	@	
	@	
HANDLING	<u>175 @ 1¹⁰</u>	<u>192⁵⁰</u>
MILEAGE	<u>4¢/sk /mile</u>	<u>140⁰⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER MARK

345 HELPER DAVE

BULK TRUCK

782 DRIVER BRENT

BULK TRUCK

DRIVER

RECEIVED
JAN 24 2003
KCC WICHITA SERVICE

TOTAL 2350⁰⁰

REMARKS:

5 S/S @ RAYHOLE
10 S/S @ MOUSEHOLE
P.C. ON JOINT #42 1757'
FLOAT HELD

DEPTH OF JOB

PUMP TRUCK CHARGE 1130⁰⁰

EXTRA FOOTAGE @

MILEAGE 20 @ 30⁰⁰ 60⁰⁰

PLUG 5 1/2 TRD @ 50⁰⁰ 50⁰⁰

@

@

TOTAL 1240⁰⁰

CHARGE TO: VENTURE RES.

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

<u>5 1/2</u>		
GUIDE SHOE	@	<u>150⁰⁰</u>
INSERT	@	<u>235⁰⁰</u>
6-CENT	@ <u>40⁰⁰</u>	<u>240⁰⁰</u>
BASKET	@	<u>142⁰⁰</u>
PORT COLLAR	@	<u>1500⁰⁰</u>

TOTAL 2267⁰⁰

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas Alon

Thomas Alon
PRINTED NAME

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

 15051 25174 0000 INVOICE *

ORIGINAL

Invoice Number: 088823

Invoice Date: 12/26/02

Sold Venture Resources Co.
 To: P. O. Box 101234
 Denver, CO
 80250-1234

RECEIVED
 JAN 24 2003
 KCC WICHITA

Cust. I.D. Vent
 P.O. Number Deane #5
 P.O. Date 12/26/02
 Due Date ... 01/25/03
 Terms ... Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	288.00	SKS	6.6500	1915.20	E
Pozmix	192.00	SKS	3.5500	681.60	E
Gel	24.00	SKS	10.0000	240.00	E
FlóSeal	120.00	LBS	1.4000	168.00	E
Handling	500.00	SKS	1.1000	550.00	E
Mileage (20)	20.00	MILE	20.0000	400.00	E
500 sks @\$.04 per sk per mi					
Top Stage	1.00	JOB	630.0000	630.00	E
Mileage pmp trk	20.00	MILE	3.0000	60.00	E

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ 464.48
 ONLY if paid within 30 days from Invoice Date

Subtotal: 4644.80
 Tax: 0.00
 Payments: 0.00
 Total: 4644.80

SECOND STAGE

ALLIED CEMENTING CO., INC. 15-051-251740000 11532

Federal Tax I.D.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

ORIGINAL
SERVICE POINT:
Russell

DATE <u>12-18-02</u>	SEC.	TWP.	RANGE	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>9:00 AM</u>	JOB START	JOB FINISH <u>1:15 PM</u>
LEASE <u>Dean</u>	WELL# <u>5</u>		LOCATION <u>HAYS N TO RR 2E Sinto</u>			COUNTY <u>Ellis</u>	STATE <u>Kn</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Chito's well service
 TYPE OF JOB Port Collon Top Stage
 HOLE SIZE 7 7/8 T.D.
 CASING SIZE 5 1/2 DEPTH
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS.
 DISPLACEMENT

OWNER _____
 CEMENT
 AMOUNT ORDERED _____
500 lb 60/40 6% gel to # Floseal
Used 480 lb

EQUIPMENT

PUMP TRUCK CEMENTER Bill
 # 177 HELPER Darin
 BULK TRUCK
 # 362 DRIVER Shane
 BULK TRUCK
 # DRIVER

COMMON	<u>288</u>	@	<u>65</u>	<u>1915.20</u>
POZMIX	<u>192</u>	@	<u>3.55</u>	<u>681.60</u>
GEL	<u>24</u>	@	<u>10.00</u>	<u>240.00</u>
CHLORIDE		@		
<u>Floseal</u>	<u>120#</u>	@	<u>140</u>	<u>168.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>500</u>	@	<u>1.10</u>	<u>550.00</u>
MILEAGE	<u>24.5</u>	/ MILE		<u>100.00</u>

RECEIVED
 JAN 24 2003
 KCC WICHITA SERVICE
 TOTAL 3954.00

REMARKS:

Port Collon e 17. Teste 100' x 1/2
open tool cement w/ 480 lb 60/40 6% gel
Floseal
Cement did Circ. close to rd press TO 130'
Ran 10' to wash clean
pull tubing

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____ 630.00
 EXTRA FOOTAGE @ _____
 MILEAGE 20 @ 3.00 60.00
 PLUG @ _____
 @ _____
 @ _____

TOTAL 690.00

CHARGE TO: Venture
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Ken Marley

PRINTED NAME