


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 35 Twp. 19S Rge. (E) 24 (W)
NW NE

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner McClure Oil Company
Lease Name BOYD "E" Well No. 1
Office Address 1301 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-24 19 69
Application for plugging filed 5-24 19 69
Application for plugging approved 5-24 19 69
Plugging commenced 5-24 19 69
Plugging completed 11:05 PM 5-24 19 69
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|--|----|--------|--------|------------|
| | | | | 8-5/8" | 495' | -0- |
| | | RECEIVED STATE CORPORATION COMMISSION JUN 2 1969 CONSERVATION DIVISION Wichita, Kansas | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

First plug at 720' with 50 sacks 50-50 Pozmix (6% gel).
Second plug at 480' with 25 sacks same.
Set solid bridge and capped with 10 sacks at 40'
Job completed at 11:05 PM, 5-24-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28 day of May, 19 69



Sherry Gish
Notary Public.
My commission expires 6-30-71

ROTARY DRILLING LOG

Operator: McClure Oil Company
 BOYD "E" #1
 NW NE 35-19S-24W
 Ness County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.
 Commenced: 5-14-69
 Completed: 5-24-69

Casing: 8-5/8"/495'/325 sx.

Formations

| | |
|----------------------------|-------|
| Surface Clay | 54' |
| Shale | 555' |
| Shale and Sand | 1045' |
| Dakota Sand | 1200' |
| Sand | 1260' |
| Red Bed | 1588' |
| Anhydrite | 1641' |
| Shale | 1960' |
| Shale and Lime Stks. | 2015' |
| Shale and Lime | 2275' |
| Lime | 2840' |
| Lime and Shale | 3945' |
| Lime | 4397' |
| Lime and Chert | 4405' |
| Miss. | 4421' |
| Lime and Chert | 4460' |
| Rotary Total Depth (D & A) | 4460' |

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct, to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains

 Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 28th day aof May, 1969.

Sherry Gish

 Sherry Gish Notary Public

My Commission Expires: _____
 June 30, 1971

