


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County. Sec. 6 Twp. 11S Rge. (E) 18 (W)
Location as "NE/CNW&SW&" or footage from lines C NW SW
Lease Owner Davis Brothers
Lease Name Gasaway P Well No. 1
Office Address 510 McFarlin Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-3 19 64
Application for plugging filed 9-3 19 64
Application for plugging approved 9-3 19 64
Plugging commenced 9-3 19 64
Plugging completed 9-3 19 64
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3675 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	167'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Bottom Plug @ 540' w/20 sx
Middle Plug @ 170' w/20 sx
Top Plug @ 40' w/10 sx

RCND
09-10-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Co.
Address 706 Union National Bldg.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.


(Signature) K. T. Woodman

706 Union National Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of Sept., 19 64

Justina Chamberlain
Notary Public.

My commission expires Feb. 11, 1968



DRILLER'S LOG

Company: Davis Brothers
 Farm: Gasaway P #1
 Total Depth: 3675'
 Comm: Aug. 24, 1964 Comp: Sept. 3, 1964
 Contractor: Woodman & Iannitti Drilling Company
 Casing: 8 5/8 @ 167' w/125 sx cement

Sec. 6-11S-18W
 Loc. C NW SW
 County: Ellis
 Elevation: 2071RB

Figures Indicate Bottom Of Formations:

0	167	Surface
167	355	Shale
355	909	Shale Stk. Sand
909	1090	Sand
1090	1155	Red Bed
1155	1335	Sand & Shale
1335	1414	Red Bed & Shale
1414	1445	Anhy.
1445	1585	Shale & Shells
1585	1860	Shale & Shells
1860	1985	Shale
1985	2040	Lime & Shale
2040	2200	Lime & Shale
2200	2250	Shale
2250	2300	Lime
2300	2380	Lime
2380	2570	Lime & Shale
2570	2675	Lime
2675	2720	Lime
2720	2850	Lime
2850	2950	Lime
2950	3075	Lime & Shale
3075	3145	Lime
3145	3225	Lime
3225	3245	Lime & Shale
3245	3305	Lime
3305	3365	Lime
3365	3390	Lime
3390	3420	Lime
3420	3450	Lime
3450	3525	Lime
3525	3550	Lime
3550	3593	Cong. & Chert
3593	3638	Lime & Chert
3638	3675	Lime
3675		Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

SEP 10 1964

CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

By: K. T. Woodman
 K. T. Woodman