

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 11 Rge. (E) 18(W)

Location as "NE/CNW&SW" or footage from lines NE NE NE

Lease Owner Chief Drilling Co., Inc.

Lease Name Gasaway Well No. 1

Office Address Ferrell Building, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed March 7, 19 57

Application for plugging filed March 7, 19 57

Application for plugging approved verbal March 6, 19 57

Plugging commenced March 7, 19 57

Plugging completed March 7, 19 57

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	206'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1/2 sack of hulls, wooden plug set at 400'; 25 sacks cement, cemented through drill pipe on top of plug.

1/2 sack of hulls, wooden plug set at 40'; 10 sacks cement, cemented through drill pipe on top of the plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor company

Address

STATE OF Kansas, COUNTY OF Barton, ss.

V. Richard Hoover, Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

CHIEF DRILLING CO., INC. (Signature) by V. Richard Hoover


Ferrell Building, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March 19 57

Emma Jean Sayre  
Emma Jean Sayre Notary Public.

My commission expires August 29, 1959



PLUGGING  
FILE SEC. 6 T. 11 R. 18W  
BOOK PAGE 146 LINE 16

RECEIVED  
CORPORATION COMMISSION  
MAR 3 - 1957  
CONSERVATION DIVISION  
Wichita, Kansas

W E L L L O G

Chief Drilling Co., Inc.  
Ferrell Building  
Great Bend, Kansas

Elevation: 1986 D.F.  
1989 K.B.

No. 1 GASAWAY

Commenced: 2/25/57  
Completed: 3/7/57

NE NE NE Sec. 6-11-18W  
Ellis County, Kansas

DRY AND ABANDONED

Contractor: Chief Drilling Co., Inc.  
Rotary: 0 - 3640' t.d.

Casing Record: 206' 48" used 28# 8 5/8" casing, set with 175 sacks Pozmix cement and 4 sacks calcium chloride; cement circulated.

Figures Indicate Bottoms of Formations

Formation Tops & Minus

Shale and Clay	0 - 205	Heebner	3208 - 1219
Shale	205 - 525	Toronto	3229 - 1240
Red Bed	525 - 550	Lansing	3249 - 1260
Red Bed & Shale	550 - 630	Base K.C.	3475 - 1486
Shale	630 - 820	Conglomerate	3555 - 1566
Sand	820 - 1010	Arbuckle	3603 - 1614
Shale and Red Bed	1010 - 1295		
Shale	1295 - 1341		
Anhydrite	1341 - 1373		
Shale and Shells	1373 - 1820		
Shale and Lime	1820 - 2300		
Lime and Shale	2300 - 2861		
Shale and Lime	2861 - 3105		
Lime	3105 - 3510		
Conglomerate	3510 - 3603		
Dolomite	3603 - 3640 t.d.		

State of Kansas )  
County of Barton )

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the NE NE NE of Sec. 6-11-18W, Ellis County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover  
V. Richard Hoover, President

Subscribed to and sworn to before me this 8th day of March, 1957.

Emma Jean Sayre  
Emma Jean Sayre, Notary Public

My commission expires:  
August 29, 1959.

RECEIVED  
STATE OF KANSAS

MAR 10 1957

CONSERVATION DIVISION  
White, Kansas

PLUGGING  
FILE SEC 6 T 11 R 18W  
BOOK PAGE 146 LINE 16