

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas, 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 6 TWP. 11SS RGE. 18W E/W
Location as in quarters or footage from lines:
NE NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Robert R. Price Operating, Inc
Lease Name Peavey C-2 Well No. _____
Office Address P.O. Box 45442 S?E. Station Tulsa, Okla. 74145
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-14-83
Plugging completed 11-16-83
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hays Ks. Office
Producing formation _____ Depth to top _____ bottom T.D.3679'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	206'	none
				5-1/2"	3678'	2407'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with 5 sacks cement and sand to 3175'. Shot casing @2711',
2612', 2506', 2403' and laved down 59 joints(2407') of 5-1/2" casing. Plugged
surface with 4 hulls, 25 cement, 15 gel, 70 cement, 5 gel, 1 hull, released plug
and displaced with 70 cement, 50/50 pos, 6% gel.
Plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of November, 19 83

My Commission expires:



Irene Hoover
Notary Public
STATE CORPORATION COMMISSION

NOV 22 1983
CONSERVATION DIVISION
Wichita, Kansas

Jed

O.W.W.O.

FIELD REPORT

DATE. November 22, 1982

OPERATOR. Robert R. Price Operating, Inc. #6273

LEASE. Peavey "C" "2"

LOCATION. SEC. 6 .TWP. 11 .RGE. 18W

COUNTY. Ellis

			•

REMARKS. (WHAT WAS SAID OR SEEN).

The above described oil well work over was drilled out this date
by Ranger Drilling Company, Inc. for Robert R. Price Operating, Inc..

Plugs were located as follows:

1st plug-0' to 40'

Old Plug-0' to 40' w/10 sx cement

2nd plug-400' to 500'

Old plug-400' w/wooden plug & 25 sx cement.

Good circulation to bottom.

STATE OF KANSAS RECEIVED
 NOV 30 1982
 CONSERVATION DIVISION
 Wichita, Kansas

FOR THE STATE. *[Signature]*

MAKE (2) TWO COPIES, KEEP ONE AND SEND ORIGINAL TO: KCC 200 COLORADO DERBY BLDG. WICHITA KANSAS 67202

2/1/48

DLS