

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Ellis County, Sec. 7 Twp. 11S Rge. 18W ~~2E~~ (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NW

NORTH



Locate well correctly on above  
Section Plat

Lease Owner Glen Rupe  
Lease Name Erisbie Well No. 1  
Office Address 222 Brown Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-4-68 19  
Application for plugging filed 5-4-68 19  
Application for plugging approved 5-4-68 19  
Plugging commenced 5-4-68 19  
Plugging completed 5-4-68 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3583 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 800' with 100 sks. 50/50 Posmix, 6% gel  
" 200' with 25 sks. " " "  
" 40' with 1/2 sk. hulls & 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 7th day of May, 19 68

My commission expires April 11, 1971  
Wanda Nichols  
Notary Public.



DRILLER'S LOG

COMPANY: Glen Rupe  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: FRISBIE #1  
 LOCATION: SW NE NW SECTION 7-11S-18W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 4-27-68  
 COMPLETED: 5-4-68

0	130	Clay, sand, post rock
130	550	Shale
550	680	Sand, shale
680	1000	Shale, sand
1000	1322	Redbed
1322	1353	Anhydrite
1353	1560	Redbed, shale
1560	2050	Shale
2050	2280	Lime, shale
2280	2480	Lime
2480	2855	Lime, Shale
2855	3000	Shale, Lime
3000	3559	Lime
3559	3583	Lime, chert
	<u>3583</u>	<u>RTD. &amp; D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 9 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

8 5/8" 20# new surface casing set @ 207' cemented with 150 sks.  
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Frisbie #1 Well, located SW NE NW of Section 7, Township 11 South, Range 18 West, Ellis County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS     )  
                           ) SS  
 COUNTY OF BARTON    ))

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of May, 1968.

Ulanda Nichols  
 Ulanda Nichols



My Commission Expires:  
 April 1, 1971