

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 16 Twp. 11S Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Lee Phillips Oil Company

Lease Name Madden Well No. 1

Office Address Wichita, Kansas Union Nat'l Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-14-53 19 53

Application for plugging filed 1-14- 19 53

Application for plugging approved 1-14 19 53

Plugging commenced 1-14 19 53

Plugging completed 1-14 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Clay		0	40			
Redbed & Shale		1150	1175			
Anhydrite		1186	1193	8 5/8	1193	None
Lime & Shale		1193	2905			
Lime		2905	3468			
T. D. Arbuckle		3490				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded Hole Up. Set wood plug at 300' ran 20 sacks of cement through drill pipe. Then mudded up to 40' set wood plug ran 1/2 sack hulls and 10 sacks of cement filling hole to the bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 20 1953  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Company

Address Box 188 Hays, Kansas.

STATE OF Kansas, COUNTY OF Ellis, ss. T. C. Strain (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. C. Strain

Box 188, Hays, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16 day of January, 19 53

Mildred Schneider Notary Public.

My commission expires March 26, 1956

PLUGGING  
FILE SEC 16 T 11 R 18  
BOOK PAGE 24 LINE 3

WELL LOG

COMPANY: Lee Phillips Oil Company

SW SW Ne Sec. 16  
Twp. 11S, Rge 18W  
Ellis County, Kansas.

LEASE: Madden # 1

ELEVATION: 1882 R. B.

NOTE: All meas Rotary Bushing

0 40 Sand & Clay  
40 160 Sand, Shells & Iron  
160 330 Shale & Shells  
330 460 Shale  
460 470 Shale  
470 530 Sand & Shale  
530 675 Shale  
675 860 Sand  
860 950 Shale & Redbed  
950 1030 Shale & Redbed  
1030 1150 Sand  
1150 1175 Redbed & Shale  
1175 1186 Hard Sand & Pyrite -  
1186 1190 Anhydrite  
1190 1193 Anhydrite  
1193 1220 Anhydrite  
1220 1735 Shale & Shells  
1735 1750 Shale & Shells  
1750 1910 Lime & Shale  
1910 1935 Lime & Shale  
1935 1950 Lime  
1950 2180 Lime  
2180 2275 Lime  
2275 2365 Shale & Lime  
2365 2390 Lime ( Hard)  
2390 2425 Lime & Shale  
2425 2530 Lime  
2530 2555 Lime  
2555 2685 Lime & Shale  
2685 2795 Lime & Shale  
2795 2905 Lime & Shale  
2905 2940 Lime  
2940 3005 Lime  
3005 3045 Lime  
3045 3064 Lime  
3064 3110 Lime  
3110 3155 Lime  
3155 3191 Lime

3191 3240 Lime  
3240 3285 Lime  
3285 3317 Lime  
3317 3370 Lime  
3370 3435 Lime  
3435 3455 Lime  
3455 3468 Lime & Shale  
3468 3490 Arbuckle  
3490 ( T. Depth )

COMMENCED: 1-2-52  
COMPLETED: 1-14-53

CASING RECORD:

8 5/8 Surface Casing set at 1193' W/500  
sacks of Posmix Cement by Halliburton

D.S.T. by Johnston Testers

3055-3064 Tool open 30 minutes. Recovered  
30' rotary mud. Weak blow for 16 Min.  
15 min. B.H.P. 920#

No Electric Logs Run

Geologist: Steve Powell

TOPS: Geologist

Topeka 2868  
Heebner 3094  
Toronto 3113  
Lansing K. C. 3135

Base K. C. 3361  
Conglomerate 3398  
Simpson 3425  
Arbuckle 3468

T. D. 3490

STATE OF KANSAS) SS  
COUNTY OF ELLIS)

**PLUGGING**  
FILE SEC 16 T 11 R 182  
BOOK PAGE 74 LINE 3

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Madden # 1, located SW SW NE, Sec. 16, Twp 11S, Rge 18W, Ellis County, Kansas.

CONTRACTOR: Strain Drilling Company

BY: T. C. Strain  
T. C. Strain.

Subscribed and sworn to before me this 15th day of January 1953.  
My commission expires March 26, 1956

Notary Public.  
Mildred Schneider