


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bitting Building
 Wichita, Kansas

15051-00790-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 18 Twp. 11 Rge. 18 (E) W (W)
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
 Lease Owner Bankoff Oil Company
 Lease Name Sites Well No. #1
 Office Address 823 North Lewis - Tulsa, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed August 3 19 54
 Application for plugging filed August 3 19 54
 Application for plugging approved August 3 19 54
 Plugging commenced August 2 19 54
 Plugging completed August 3 19 54
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
 Producing formation Depth to top Bottom Total Depth of Well Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1223'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged by Halliburton with pouring 75 sx. cement through a switch.

RECEIVED
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Anschutz Drilling Co., Inc. AUG 4 1954
 Address 706 Union National Bank Building
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
 E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. G. Koelling*
 706 Union National Bank Building
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 54

Chelene A. Bean
 Notary Public.

My commission expires February 27, 1956.

PLUGGING
 FILE SEC 18 T 11 R 1100
 BOOK PAGE 53 LINE 31

24-7968-5 3-53-20M

DRILLER'S LOG

Bankoff Oil Co.
 Sites #1
 NE NE SW 18-11-18
 Ellis County, Kansas

<u>TO</u>	<u>FROM</u>	
0	100	Surface Soil & Shale
100	120	Sand
120	485	Shale & Shells
485	690	Shale & Sand Streaks
690	900	Dakota Sand
900	933	Red Bed & Shale
933	1221	Shale & Red Bed
1221	1260	Anhydrite
1260	1775	Shale & Shells
1775	1980	Shale & Lime
1980	2245	Lime
2245	2360	Lime & Shale
2360	2545	Shale & Lime
2545	2660	Lime & Shale
2660	3040	Shale & Lime
3040	3097	Lime
3097	3180	Shale & Lime
3180	3380	Lime
3380	3435	Lime & Shale
3435	3445	Cherty Cong.
3445	3468	Shale & Lime
3468	3485	Chert
3485	3508	Lime
3508	3521	Conglomerate
3521	3540	Arbuckle
	3540	ROTARY TOTAL DEPTH
		D & A

COMMENCED: 7-22-54
 COMPLETED: 8-3-54

CASING RECORD:

Set 1223' of 8 5/8" casing with
 475 sacks of cement.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Sites #1 located NE NE SW of Section 18-11-18, Ellis County, Kansas.

ANSCHUTZ DRILLING CO., INC.

RECEIVED
 STATE OF KANSAS
 AUG 12 1954
 DEPT. OF REVENUE

BY: E. G. Koelting
 E. G. Koelting

Subscribed and sworn to before me this 4th day of August, 1954.

Abeline A. Bean
 Notary Public

My Commission Expires: February 27, 1956.

PLUGGING
 FILE SEC 18 T 11 R 18 W
 BOOK PAGE 53 LINE 31