

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078 130 S. Market
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R. -82-3-117

API NUMBER 15-025-20-971-0001

LEASE NAME Van Blaricum "A"

WELL NUMBER 1

3570' Ft. from S Section Line

1729' Ft. from E Section Line

SEC. 29 TWP. 32 RGE. 22 (E) or (W)

COUNTY Clark

Date Well Completed _____

Plugging Commenced 9-9-98

Plugging Completed 9-11-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Comm. Div.
 office within 30 days.

LEASE OPERATOR PETROFIELD SERVICES CORPORATION

ADDRESS R.R. # 5, Box 104 Chickasha, Oklahoma 73018

PHONE (405) 224-1113 OPERATORS LICENSE NO. 31330

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 25, 1998 (date)

by Steve Barnett (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? N/A

Producing Formation _____ Depth to Top 4494' Bottom 4498' T.O. 4920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		4494'	4498'	8-5/8	828'	0
				5-1/2	4865'	4025'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Shot off 2-7/8" tubing @ 4860', pumped 50 sxs. class A cement plug 4860' to 4325', load hole with plug mud, shot 5-1/2" casing-off @ 4025', pumped 50 sxs. cement plug 1225' to 990', pumped 50 sxs. cement plug 865' to 720', pumped 25 sxs. cement plug 465' to 250', pumped 15 sxs. plug 34' to 4'.

Name of Plugging Contractor PETROFIELD SERVICES CORPORATION License No. 31330

Address R.R. #5, Box 104 Chickasha, Oklahoma 73018

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROFIELD SERVICES CORPORATION

STATE OF OKla COUNTY OF Grady, ss.

Ed Lively


(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ed Lively

(Address) Rt 5 Box 104 Chickasha, OK 73018

SUBSCRIBED AND SWORN TO before me this 16 day of Sept, 19 98



Jimmie Landis
 Notary Public

My Commission Expires: 7-22-2000