

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days

API NUMBER 15-077-21434 -0000
LEASE NAME Watt A
WELL NUMBER 1
3960 ft. from S Section Line
660 ft. from E Section Line
SEC. 7 TWP. 33 RGE. 6 (E) or (W)

RECEIVED

APR 17 2003

LEASE OPERATOR Pintail Petroleum
ADDRESS 225 N. Market, Wichita, KS 67202

KCC WICHITA

PHONE # (319) 263-2243 OPERATORS LICENSE NO. 5086

Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 4/2/03 (date)

by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4518

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	259	none
				4 1/2	4517	3548

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 4432, bailed 4 sacks cement. Shot pipe at 3940, 3710, 3548, work free. Pull to 1150, pump 35 sacks cement. Pull to 800', pump 35 sacks cement. Pull to 300, circulate cement to surface with 130 sacks cement. Pulled rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum

STATE OF Kansas COUNTY OF Sedgwick, ss.

Beth A. Isern (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Beth A. Isern

(Address) 225 N. Market, Ste. 300, Wichita KS


SUBSCRIBED AND SWORN TO before me 17 day of April, 2003

Susan Utterback

Notary Public

My commission Expires: 9/7/2006

Form CP-4
Revised 05-88



Ba