


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 17 Twp. 33S Rge. 7W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines 150' SW of SE NE SW  
Lease Owner Walters Drilling Co., et al  
Lease Name Fox Well No. 1  
Office Address 510 Orpheum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 25, 1964 19  
Application for plugging filed June 24, 1964 19  
Application for plugging approved June 25, 1964 19  
Plugging commenced June 25, 1964 19  
Plugging completed June 25, 1964 19

NORTH



Locate well correctly on above  
Section Plat

Reason for abandonment of well or producing formation  
commercial quantities of oil not found  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4980 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug @ 215' w/ 25 sx. cement.  
Set top plug @ 40' w/ 10 sx. cement.  
2 sx. cement in rat hole.

RECEIVED  
CORPORATION DIVISION

JUL 1 1964

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robert F. Walters (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
510 Orpheum Building, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 30th day of June, 19 64  
Juanita M. Green  
Notary Public.

My commission expires October 4, 1967



DRILLER'S LOG

COMPANY: WALTERS DRILLING CO., ET AL  
 510 ORPHEUM BUILDING  
 WICHITA, KANSAS

WELL NAME: FOX #1  
 LOCATION: 150' SW of SE NE SW Sec. 17-33S-7W  
 HARPER COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.  
 510 ORPHEUM BUILDING  
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: JUNE 8, 1964  
 ROTARY DRILLING COMPLETED: JUNE 25, 1964

ELEVATION: 1341 KB  
 1338 DF  
 1336 GL

CASING RECORD: 8 5/8" set @ 215' w/ 160 sacks cement

LOG

0 - 20	Surface Soil
20 - 430	Shale
430 - 1245	Shale and Shells
1245 - 1320	Shale and Lime
1320 - 1750	Lime and Shale
1750 - 1875	Lime
1875 - 1990	Chalky Lime and Shale
1990 - 2530	Lime and Shale
2530 - 2902	Shale and Lime
2902 - 3213	Lime and Shale
3213 - 3613	Shale and Lime
3613 - 3708	Shale, Sand and Lime
3708 - 3780	Sand
3780 - 4060	Lime and Shale
4060 - 4125	Lime
4125 - 4175	Lime and Shale
4175 - 4298	Lime
4298 - 4415	Lime and Shale
4415 - 4478	Lime
4478 - 4550	Lime and Shale
4550 - 4565	Cherty Lime
4565 - 4870	Lime
4870 - 4935	Lime and Shale
4935 - 4966	Lime
4966 - 4980	Lime and Sand
<u>4980</u>	<u>Rotary Total Depth - D &amp; A</u>

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL -1 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

*Robert F. Walters*  
ROBERT F. WALTERS, Partner

STATE OF KANSAS )

SS.

COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 30th day of June, 1964, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came Robert F. Walters, known to me to be the same person who executed the foregoing instrument as Partner and in behalf of the Walters Drilling Co. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:  
October 4, 1967

*Janita M. Green*  
Janita M. Green, Notary Public

